



**ADDENDUM NO. 1  
CONTRACT: RDSO 1801  
DATED: AUGUST 6, 2018**

**TOWN OF RIVERHEAD  
RIVERHEAD SEWER DISTRICT**

**841 OLD COUNTRY ROAD SEWER MAIN & EASEMENT RELOCATION**

**1. DELIVERY VIA EMAIL CONFIRMATION TO ALL REGISTERED BIDDERS  
THROUGH E-NOTIFICATIONS ON TOWN OF RIVERHEAD WEBSITE**

*This Addendum is hereby made a part of the Contract Documents for the above noted project and construction contract and modifies the Original Bidding Documents. The Bidder shall note the following clarifications, deletions, additions, and changes to the Contract Documents and shall submit his/her bid and be otherwise governed accordingly. Failure to acknowledge the Addendum may subject the Bidder to disqualification.*

**Bidder shall note the following:**

1. Acknowledge receipt of the Addendum on page PB-4 located in the Contract Book of the Bid Documents.
2. Addendum No. 1 for Project No. RDSO 18-01 consists of 3 pages in total. Pages 1 and 2 of this addendum consist of written changes to the Project Manual. The third page of this Addendum consists of a soil boring log to be included as a document for information only at the end of the Project Manual.

**PROJECT MANUAL**


**A. INFORMATION ONLY DOCUMENTS:**

1. INSERT THE ATTACHED SOIL BORING LOG AT THE END OF THE PROJECT MANUAL. THE LOCATION OF THE SOIL BORING IS ALONG THE EAST SIDE OF OSTRANDER AVENUE, APPROXIMATELY 50 FEET SOUTH OF THE INTERSECTION OF OLD COUNTRY ROAD AND OSTRANDER AVENUE.

**B. CONDITIONS OF CONTRACT:**

1. PARAGRAPH 10. CONTRACT SECURITY: DELETE THE ENTIRE FIRST PARAGRAPH AND REPLACE WITH "THE CONTRACTOR SHALL FURNISH A PERFORMANCE BOND EQUAL TO 100% OF THE ESTIMATED VALUE OF THE PROJECT(S) TO BE COMPLETED UNDER THIS CONTRACT."

**CONTRACT NO. RDSO 18-01**





**ADDENDUM NO. 1**  
**CONTRACT: RDSB 1801**  
**DATED: AUGUST 6, 2018**

**TOWN OF RIVERHEAD**  
**RIVERHEAD SEWER DISTRICT**

**841 OLD COUNTRY ROAD SEWER MAIN & EASEMENT RELOCATION**

A: NBONO@H2M.COM | PM: | LSB: NICHOLAS F. BONO |  
LSD: 8/6/2018 9:51 AM | LPD: 8/6/2018 9:51 AM | 20 JANUARY 2017| R#: 6 | P: 2 |  
X:\RDSB (RIVERHEAD SEWER DISTRICT) - 10805\RDSB1801 841 OLD COUNTRY RD DESIGN\03-  
BID\ADDENDA\RDSB 1801 - CONTRACT ADDENDUM NO.1.DOC |  
ADDENDUM NO. 1 | RDSB 1801 |

# MUNICIPAL TESTING LABORATORY, INC.

AN ENGINEERING INSPECTION AND TESTING COMPANY

375 RABRO DRIVE, HAUPPAUGE, NY 11788 - PH: (631)761-5555; FAX (631)761-5560

CLIENT:	H2M Architects + Engineers	BORING #:	1
PROJECT:	Prohealthcare	PERCOLATION TEST #:	
	Old Country Rd. and Ostrander Ave.,	DEPTH OF HOLE:	16'
	Riverhead, NY	ROCK CORE:	
DATE DRILLED:	12/14/16	ROCK RECOVERY:	
DRILLER:	Dave Johnson		
HELPER:		SURFACE ELEVATION:	
TYPE OF RIG:	GEOPROBE	GROUND WATER TABLE:	NA

DEPTH BELOW SURFACE	SAMPLE NUMBER	BLOWS PER 6" ON SAMPLER		CASING BLOWS PER FT.	SOIL SAMPLE DESCRIPTION	BEARING CAPACITY	DRILLING REMARKS
5	S1	5	5		22" CBS		GPR USED ONSITE
		5	5				CBS-Coarse Brown Sand
	S2	3	3		21" CBS		
		3	3				
10	S3	4	4		21" CBS		
		3	3				
	S4	5	4		23" CBS		
		5	5				
15	S5	8	7		16" CBS		
		6	7				
	S6	9	7		20" CBS		
		6	7				
20	S7	8	6		20" CBS		
		6	5				
	S8	5	4		20" CBS		
		6	7				
25							
30							
35							

STEPHEN M. LATUS, PE

SEE BORING LOCATION PLAN IN THE FOLLOWING PAGE